

February 2017

NASA COMMERCIAL CREW PROGRAM

Schedule Pressure Increases as Contractors Delay Key Events

GAO Highlights

Highlights of GAO-17-137, a report to congressional committees

Why GAO Did This Study

Since the Space Shuttle was retired in 2011, the United States has been relying on Russia to transport astronauts to and from the ISS. The purpose of NASA's Commercial Crew Program is to facilitate the development of a domestic transport capability. In 2014, NASA awarded two firm-fixed-price contracts to Boeing and SpaceX with a combined total value up to \$6.8 billion for the development of crew transportation systems that meet NASA requirements and initial missions to the ISS. The contractors were originally required to provide NASA all the evidence it needed to certify that their systems met its requirements by 2017.

A house report accompanying H.R. 2578 included a provision for GAO to review the progress of NASA's human exploration programs. This report examines the Commercial Crew Program including (1) the extent to which the contractors have made progress towards certification, (2) the risks facing the program, and (3) the extent to which the program has visibility into the contractors' efforts. To do this work, GAO analyzed contracts, schedules, and other documentation; and spoke with officials from NASA, the Commercial Crew Program, Boeing, SpaceX, and independent review bodies.

What GAO Recommends

Given the delays in the Commercial Crew Program, GAO recommends that NASA develop and report to Congress on its contingency plans for maintaining a U.S. presence on the ISS beyond 2018. NASA concurred with the recommendation and intends to develop a contingency plan.

View GAO-17-137. For more information, contact Cristina T. Chaplain at (202) 512-4841 or chaplainc@gao.gov.

NASA COMMERCIAL CREW PROGRAM

Schedule Pressure Increases as Contractors Delay Key Events

What GAO Found

Both of the Commercial Crew Program's contractors have made progress developing their crew transportation systems, but both also have aggressive development schedules that are increasingly under pressure. The two contractors—Boeing and Space Exploration Technologies, Corp. (SpaceX)—are developing transportation systems that must meet the National Aeronautics and Space Administration's (NASA) standards for human spaceflight-a process called certification. Both Boeing and SpaceX have determined that they will not be able to meet their original 2017 certification dates and both expect certification to be delayed until 2018, as shown in the figure below. The schedule pressures are amplified by NASA's need to provide a viable crew transportation option to the International Space Station (ISS) before its current contract with Russia's space agency runs out in 2019. If NASA needs to purchase additional seats from Russia, the contracting process typically takes 3 years. Without a viable contingency option for ensuring uninterrupted access to the ISS in the event of further Commercial Crew delays, NASA risks not being able to maximize the return on its multibillion dollar investment in the space station.



Source: GAO analysis of National Aeronautics and Space Administration contracts and documents. | GAO-17-137

Both contractors are also dealing with a variety of risks that could further delay certification, including program concerns about the adequacy of information on certain key systems to support certification. Another top program risk is the ability of NASA and its contractors to meet crew safety requirements.

The Commercial Crew Program is using mechanisms laid out in its contracts to gain a high level of visibility into the contractors' crew transportation systems. The program is using a different model than every other spacecraft NASA has built for humans. For example, NASA personnel are less involved in the testing, launching, and operation of the crew transportation system. The program has developed productive working relationships with both contractors, but the level of visibility that the program has required thus far has also taken more time than the program or contractors anticipated. Ultimately, the program has the responsibility for ensuring the safety of U.S. astronauts and its contracts give it deference to determine the level of visibility required to do so. Moving forward though, the program office could face difficult choices about how to maintain the level of visibility it feels it needs without adding to the program's schedule pressures.

United States Government Accountability Office

Contents

Letter		1
	Background	3
	Neither Contractor Expects to Achieve Certification before 2018 and NASA Has Not Yet Determined How It Will Ensure ISS	
	Access in Case of Further Delays	9
	Crew Program Has Visibility into Contractor Progress, but Maintaining Its Current Level of Visibility through Certification	14
	Could Add to Schedule Pressures	18
	Conclusions	24
	Agency Comments and Our Evaluation	20 25
	Agency comments and our Evaluation	20
Appendix I	Objectives, Scope, and Methodology	26
Appendix II	Commercial Crew Program Phases and Participants	29
Appendix III	Comments from the National Aeronautics and	
	Space Administration	30
Appendix IV	GAO Contact and Staff Acknowledgments	32
Tables		
	Table 1: Differences in the Information Provided on Two Human Space Flight Projects in NASA's Fiscal Year 2017 Budget	8
	Table 2: Commercial Crew Program Uses Three Contractually- Defined Mechanisms to Gain Visibility into the	
	Contractors' Crew Transportation Systems	20
	Table 3: Commercial Crew Program Phases, Contractors, and Level of Funding	29
Figures		

Figure 1: Boeing and SpaceX Crew Transportation Systems

5

11
12
21

Abbreviations

Page ii

FAR	Federal Acquisition Regulation
ISS	International Space Station
NASA	National Aeronautics and Space Administration
SpaceX	Space Exploration Technologies Corporation
ULA	United Launch Alliance

This is a work of the U.S. government and is not subject to copyright protection in the United States. The published product may be reproduced and distributed in its entirety without further permission from GAO. However, because this work may contain copyrighted images or other material, permission from the copyright holder may be necessary if you wish to reproduce this material separately.

U.S. GOVERNMENT ACCOUNTABILITY OFFICE

441 G St. N.W. Washington, DC 20548

February 16, 2017

The Honorable Richard Shelby Chairman The Honorable Jeanne Shaheen Ranking Member Subcommittee on Commerce, Justice, Science, and Related Agencies Committee on Appropriations United States Senate

The Honorable John Culberson Chairman The Honorable José Serrano Ranking Member Subcommittee on Commerce, Justice, Science, and Related Agencies Committee on Appropriations House of Representatives

Following the retirement of the Space Shuttle in 2011, the United States was left with no domestic ability to provide crew access to the International Space Station (ISS). Since then, the National Aeronautics and Space Administration (NASA) has relied on purchasing seats from Russia on its Soyuz spacecraft to maintain a U.S. presence on the station. NASA's Commercial Crew Program is intended to end this dependency by facilitating the commercial development of a crew transportation system that can provide safe, reliable, and cost-effective transportation to and from the ISS no later than 2017. NASA's goal is to have one or more contractors that can provide crew transportation services to the ISS, which is planned to be operational until at least 2024.

NASA's acquisition strategy on the Commercial Crew Program is similar to the one it used successfully on the Commercial Cargo program, but different than every other spacecraft it has built for humans, from Mercury to Gemini and Apollo to the Space Shuttle. Each contractor designs, develops, builds, owns, and operates its spaceflight system and infrastructure. The contractors have access to NASA's expertise and resources throughout the development process, but NASA engineers are not making design decisions and NASA personnel will be less involved in processing, testing, launching, and operating the crew transportation system. In the end, NASA will buy a crew transportation service—a ride for its astronauts to and from the ISS—much like it does for ISS cargo. In the most recent phase of the Commercial Crew Program, NASA awarded firm-fixed-price contracts in 2014 to Boeing and Space Exploration Technologies Corporation (SpaceX), valued at up to \$4.2 billion and \$2.6 billion, respectively, for the development of crew transportation systems that meet NASA requirements and initial missions to the ISS. According to the contracts, the companies are supposed to provide NASA all the evidence it needs to certify that their systems meet its performance and safety requirements by 2017.

The House Committee on Appropriations report accompanying H.R. 2578 includes a provision for us to review the acquisition progress of NASA's human exploration programs, including the Commercial Crew Program. For this review, we assessed (1) the extent to which the contractors have made progress towards certification and the potential effects of any certification delays on NASA's access to the ISS; (2) the major programmatic and safety risks facing the program and the contractors; and (3) the extent to which the program has visibility into the contractors' efforts. To assess the contractors' progress toward certification, we reviewed program and contract documents, including guarterly progress updates and monthly schedule summaries, as well as interviewed program and contractor officials. We also reviewed information from NASA's budget, its contract with the Russian Federal Space Agency, and the ISS program to determine how NASA plans to mitigate the effects of any certification delays on its access to the ISS. To assess major programmatic and safety risks, we analyzed the program's monthly risk charts and contractor documentation. We also interviewed program and contractor officials to identify steps being taken to mitigate risks. To assess the program's visibility into the contractors' efforts, we reviewed program and contract documents, interviewed officials to identify mechanisms NASA uses to gain visibility into the contractors' efforts, and observed how these mechanisms functioned in practice for several key contract events. For these events, we interviewed program and contractor officials to learn how NASA uses various mechanisms to gain visibility, analyzed supporting documents, and compared NASA's visibility to what is defined in the contract. For all three objectives, we met with independent NASA expert groups to corroborate information we received from the program and its contractors. Appendix I contains detailed information about our scope and methodology.

We conducted this performance audit from March 2016 to February 2017 in accordance with generally accepted government auditing standards. Those standards require that we plan and perform the audit to obtain sufficient, appropriate evidence to provide a reasonable basis for our

findings and conclusions based on our audit objectives. We believe that the evidence obtained provides a reasonable basis for our findings and conclusions based on our audit objectives.

Background	NASA's Commercial Crew Program is a multi-phased effort that began in 2010. Across the five phases, NASA has engaged several companies using both agreements and contract vehicles to develop and demonstrate crew transportation capabilities. As the program has passed through these phases, NASA has generally narrowed down the number of participants. The early phases of the program were under Space Act agreements, which is NASA's other transaction authority. ¹ These types of agreements are generally not subject to the Federal Acquisition Regulation (FAR) and allow the government and its contractors greater flexibility in many areas. Under these Space Act agreements, NASA relied on the commercial companies to propose specifics related to their crew transportation systems, including their design, the capabilities they would provide, and the level of private investment. In these phases, NASA provided technical support and determined if the contractors met certain technical milestones. In most cases, NASA also provided funding. For the final two phases of the program, NASA awarded FAR-based contracts. By using FAR-based contracts, NASA gained the ability to levy specific requirements on the contractors and procure missions to the ISS, while continuing to provide technical expertise and funding to the contractors. Under the contracts, NASA will also evaluate whether contractors have met its requirements and certify their final systems for use. Appendix II contains a description of each of the Commercial Crew Program's phases, a list of the participants, and the level of funding provided to each participant by NASA.
Program Requirements	Before a company's crew transportation system can be certified by NASA, it must meet two sets of requirements. The ISS program levies a set of 332 requirements that must be met by all visiting spacecraft, whether they are carrying cargo or crew to the station. There are three major areas outlined in the ISS requirements document: 1) interface requirements for both the ISS and the spacecraft; 2) performance requirements for ground systems supporting the spacecraft; and 3)

¹This authority allows an agency to enter into agreements "other than" standard government contracts or other traditional mechanisms.

design requirements for spacecraft to ensure safe integration with the ISS. The second set of requirements is levied by the Commercial Crew Program. These include 280 high-level requirements related to the design, manufacturing, testing, qualification, production, and operation of crew transportation systems that deliver NASA astronauts to the ISS. Contractors are responsible for developing the lower-level system specifications and system and subsystem designs that implement those requirements. For example, there is a Commercial Crew Program requirement for the contractor's crew transportation system to provide a continuous autonomous launch abort capability, in which the spacecraft self-initiates the abort procedure independent from the supporting ground systems, from lift-off through orbital insertion with a 95 percent probability of success. The requirement does not specify how elements of the crew transportation system, such as its sensors, software, propulsion, or capsule, should be designed to fulfill it.

Current Program Contracts

In September 2014, NASA awarded firm-fixed-price contracts to Boeing and SpaceX, valued at up to \$4.2 billion and \$2.6 billion, respectively, for the Commercial Crew Transportation Capability phase. Under a firmfixed-price contract, the contractor must perform a specified amount of work for the price negotiated by the contractor and government. This is in contrast to a cost-reimbursement contract, in which the government agrees to pay the contractor's reasonable costs regardless of whether work is completed. During this phase, the contractors will complete development of crew transportation systems that meet NASA requirements, provide NASA with the evidence it needs to certify that those systems meet its requirements, and fly initial crewed missions to the ISS. Under the contracts, NASA and the companies originally planned to complete the certification review for each system by 2017. Figure 1 shows the spacecraft and launch vehicles for Boeing and SpaceX's crew transportation systems.

Figure 1: Boeing and SpaceX Crew Transportation Systems



Source: Copyright © 2016 United Launch Alliance, LLC. (top image); @2016 SpaceX (bottom image). | GAO-17-137

The Commercial Crew Transportation Capability phase contracts include three types of services:

- **Contract Line Item 001** encompasses the firm-fixed-price design, development, test, and evaluation work needed to support NASA's final certification of the contractor's spacecraft, launch vehicle, and ground support systems.
- **Contract Line Item 002** covers any service missions that NASA orders to transport astronauts to and from the ISS. Under this

indefinite-delivery, indefinite-quantity line item, NASA must order at least two missions from each contractor, which it has done, and can order up to six missions. Each service mission is its own firm-fixed-price task order. NASA must certify the contractors' systems before they can fly these missions.²

• **Contract Line Item 003** is an indefinite-delivery, indefinite-quantity line item for any special studies, tests, and analyses that NASA may request. These tasks do not include any work necessary to accomplish the requirements under contract line item 001 and 002. As of September 2016, NASA had issued one order under this contract line item to Boeing—an approximately \$180,000 study of the spacecraft's seat incline. The maximum value of this contract line item is \$150 million.

NASA divided the certification work under contract line item 001 into two acceptance events: the ISS design certification review and the certification review. An acceptance event occurs when NASA approves a contractor's designs and acknowledges that the contractor's work is complete and meets the requirements of the contract. The ISS design certification review verifies the contractor's crew transportation system's capability to safely approach, dock, mate, and depart from the ISS, among other requirements. After the contractor has successfully completed all its flight tests, as well as various other activities, the certification review determines whether the crew transportation system meets the Commercial Crew Program's requirements. The contractors must complete both acceptance events to receive NASA certification.

NASA and the contractors also identified discrete performance-based events, called interim milestones, which occur as the contractors progress towards the two acceptance events. Each interim milestone has predetermined entrance and exit criteria that establish the work that must be completed in order for the contractor to receive payment. The interim milestones serve several functions, allowing the government to finance work from development to completion, review the contractors' progress, and provide approval to proceed with key demonstrations and tests. These milestones are also used by the program to inform its annual budget request. Since the contracts were awarded, the Commercial Crew Program and the contractors have agreed to split several of the interim

²An indefinite-delivery, indefinite-quantity contract is used to acquire supplies or services during a specified contract period when the exact times and exact quantities of future deliveries are not known at the time of contract award.

milestones. The contractors have also added new milestones, in part to capture changes in their development plans.

NASA has also made changes to the contracts that have increased their value. While the contracts are fixed-price, their values can increase if NASA adds to the scope of the work or otherwise changes requirements. As of October 2016, NASA had increased the value of contract line item 001 for Boeing by \$47 million for hardware and software requirement changes, and contract line item 001 for SpaceX by \$91 million for a hardware requirement change and the addition of cargo during an ISS test flight.

Program Oversight

NASA has tailored its management approach for the Commercial Crew Program because the contractors, not the government, are responsible for the design, development, test, and evaluation of their crew transportation systems and make their own decisions about when to build, integrate, and test hardware. For example, NASA policy outlines key decision point reviews, which allow NASA management to determine if the program is ready to progress to the next phase.³ NASA management relies on annual program reviews, instead of key decision point reviews, to provide oversight of the Commercial Crew Program. According to NASA management officials, they chose to do so because the contractors' development approaches and schedules did not align with NASA's typical key decision points. Other elements of the reviews are similar though. For example, NASA's first annual review of the program included updates on overall program risk, an update on the program's cost and schedule risks, and perspectives from the independent review board, much like a key decision point review. The firm-fixed price nature of the current contracts also led NASA to alter its typical management approach. For example, the NASA Associate Administrator told us that he decided not to require an agency baseline commitment—cost or schedule baseline—for the Commercial Crew Program, in part, because the firm-fixed-price contracts with each contractor essentially serve as the cost baselines for the program.

NASA also provides regular updates to Congress on the Commercial Crew Program through a variety of reporting mechanisms. NASA includes

³NASA Procedural Requirements 7120.5E NASA Space Flight Program and Project Management Requirements (Aug. 14, 2012).

information on all of its major projects, including Commercial Crew, in its annual budget submission, although the type and specificity of the information can differ. For example, table 1 shows the key differences in the types of information NASA provided on two human space flight projects—the Commercial Crew Program and the Orion Crew Vehicle development in its fiscal year 2017 budget request. In addition to its budget, NASA submits quarterly reports to the appropriations committees on the Commercial Crew Program's progress that include cost and schedule updates from each contractor and information on contractor specific-risks, including procurement-sensitive material that is not publically releasable.

Type of Information	Orion Crew Vehicle Development Program	Commercial Crew Program
Budget authority	Included prior funding received, funding requested for fiscal year 2017, notional funding requests for the next 4 years, and additional funding needed to complete the program	Included funding requested for fiscal year 2017 and notional funding requests for the next 4 years
Program schedule	Listed key program milestones, committed dates from the program's baseline, current estimates based on the budget request, and overall program delay	Included the fiscal years for each of the phases of the Commercial Crew Program, total number of contractor milestones, and number and percentage of contractor milestones completed
Program cost	Provided the total baseline and current development cost estimate, a breakdown of those development costs, percentage cost changes, and joint cost and schedule confidence level associated with the baseline estimate	Provided the total potential value for the milestones associated with the design, development, test, and evaluation portion of the current contracts and the funding provided for completed milestones
Program risks	Briefly described three program risks, the potential effect of those risks on the program, and mitigation plans	No discussion of program risks

Table 1: Differences in the Information Provided on Two Human Space FlightProjects in NASA's Fiscal Year 2017 Budget

Source: GAO analysis of NASA data. | GAO-17-137

Neither Contractor Expects to Achieve Certification before 2018 and NASA Has Not Yet Determined How It Will Ensure ISS Access in Case of Further Delays	Since September 2014, both Boeing and SpaceX have made progress developing their crew transportation systems, but neither contractor will be able to meet their original 2017 certification dates and both expect certification to be delayed until 2018. As the contractors have fallen behind, the time between key test events has decreased, which reduces the time the contractors have to learn and implement changes, increasing the likelihood of additional delays. The schedule pressures are amplified by NASA's need to provide a viable crew transportation option to the ISS before its current contract with Russia's space agency runs out in 2019. NASA has not yet developed a contingency plan to ensure an uninterrupted presence on the ISS should the Commercial Crew Program experience further delays, although the ISS program has begun to discuss potential options.
Both Contractors Have Begun Manufacturing Spacecraft and Modifying Launch Facilities	Both Boeing and SpaceX have made progress finalizing their designs and building hardware as they work towards final certification of their crew transportation systems. Each contractor's system includes a spacecraft and a launch vehicle with supporting ground systems. Examples of the contractors' development progress since September 2014 include the following:
	• Boeing: In 2015, Boeing completed its critical design review, which determines whether a system's design is stable enough to proceed with final design and fabrication, and began fabricating the first of its three planned spacecraft. This spacecraft will be tested to validate the design, including in a planned January 2018 pad abort test where the ability of the capsule's abort system is tested from a static position on the launch pad. Further, in May 2016, Boeing shipped the structural test article for its service module to its testing facility and shipped the crew module in January 2017. These modules will be used to conduct tests that simulate different operating environments, such as the vibrations during a launch ascent, on key spacecraft components. Boeing and its launch vehicle provider, United Launch Alliance (ULA), have also made significant modifications to its launch facilities at the Cape Canaveral Air Force Station, including installing a crew access tower and crew access arm, which the crew will use to board the crew capsule prior to launch.
	 SpaceX: SpaceX completed its critical design review in 2016 and has begun assembling and integrating components of the two spacecraft it will use for its uncrewed and crewed flight tests, which are scheduled for November 2017 and May 2018, respectively. SpaceX officials told us they completed integrated testing and qualification of several major

	spacecraft components, including its environmental control and life support system—which controls air quality and temperature, among other functions, to ensure crew survivability—and its spacesuit in November 2016. SpaceX also made significant modifications to its launch facilities at the Kennedy Space Center, including constructing a new hangar and an upgraded flame trench, which is critical to safely contain the plume exhaust from rocket launches, and substantially upgrading the existing crew access tower, which was last used during the Space Shuttle era.
Both Contractors Have Delayed Certification and Reduced Time between Key Test Events	Neither Boeing nor SpaceX will be able to meet their original 2017 certification dates and both now expect certification to be delayed until 2018. Since the award of the current Commercial Crew contracts, the program, Boeing, and SpaceX have all identified the contractors' delivery schedules as aggressive. Program officials told us that, from the outset, they knew delays were likely due to the development nature of the program. Multiple independent review bodies—including the program's standing review board, the Aerospace Safety Advisory Panel, and the NASA Advisory Council-Human Exploration and Operations committee— also noted the aggressiveness of the contractors' schedules as they move toward certification.
	Both contractors have notified NASA that they would not be able to meet the 2017 certification dates originally established in their contracts. These notices required the parties to renegotiate their contracts to reflect the contractors' delays. As of October 2016, both contractors have submitted, and NASA has agreed to, updated schedules that reflect delays to their final certification review dates—Boeing by 5 months, from August 2017 until January 2018, and SpaceX by 6 months, from April 2017 until October 2017. Boeing and SpaceX's internal schedules both show additional certification delays that, as of November 2016, were not yet reflected in their contracts. As the contractors have made changes to their development schedules, they have also reduced the number of months between critical test events leading up to final certification, which reduces the time the contractors have to learn, make any needed design changes, and implement those changes, increasing the likelihood of additional delays. Figures 2 and 3 below show the total proposed certification delay and current proposed schedule for each contractor.





ISS = International Space Station

Source: GAO analysis of National Aeronautics and Space Administration contracts and documents. | GAO-17-137

Note: The uncrewed and crewed flight tests are not contract milestones for Boeing. The dates for these events are from other Boeing or Commercial Crew Program documentation.

Since Boeing and the Commercial Crew Program agreed to move Boeing's certification review from August 2017 to January 2018, Boeing has proposed moving the review out by at least 9 additional months to the fourth quarter of 2018. The current proposed schedule is the fourth significant schedule change by Boeing since the contract was awarded. The most recent schedule update includes delays related to a manufacturing error. In September 2016, a subcontractor damaged a major component of Boeing's second spacecraft during machining to trim mass from the spacecraft. This is expected to delay delivery of the component by 2-3 months, which is reflected in the current proposed schedule. The second spacecraft is important because, according to Boeing's program schedule, it will be used to support a significant portion of Boeing's planned testing as well as its crewed flight test.

Boeing also reduced the time between some key testing events that will be used to provide data necessary for Boeing to demonstrate its ability to meet NASA's requirements. In the original schedule, Boeing allocated 3 months between its uncrewed flight test and its crewed flight test, but under its current proposed schedule, there are only 2 months between these critical test events. Although these events are not formal milestones in Boeing's contract with NASA, they are critical learning events, and we have previously found that reducing the time between key test events limits time for the contractor to learn and adapt to any changes that may be required.⁴ Boeing is also tracking a risk that the schedule could be further delayed because there is little time between test events.



ISS = International Space Station

Source: GAO analysis of National Aeronautics and Space Administration contracts and documents. | GAO-17-137

Since SpaceX and the Commercial Crew Program agreed to move its certification review from April 2017 to October 2017, SpaceX has proposed moving the review out by at least 9 additional months to the third quarter of 2018. SpaceX officials stated that these delays are largely driven by development challenges, changes in NASA requirements, and implementation of corrective actions stemming from a launch vehicle mishap in 2016. On September 1, 2016, SpaceX experienced an anomaly during a standard, pre-launch static fire test of its Falcon 9 launch vehicle that resulted in an explosion and the loss of the vehicle. The mishap investigation is complete and SpaceX returned to flight in January 2017 with a commercial launch. However, additional schedule changes are possible. SpaceX officials told us that they continue to assess the effect of the mishap on their Commercial Crew schedule. Further, as SpaceX has made schedule changes, it has also reduced the time between its uncrewed flight test and crewed flight test from 7 months to 6 months.

⁴GAO, NASA: Assessments of Major Projects, GAO-16-309SP (Washington, D.C.: Mar. 30, 2016).

The Commercial Crew Program is tracking risks that both contractors could experience additional schedule delays and its own analysis indicates that certification is likely to slip into 2019. One of the program's top six programmatic risks for each contractor is the likelihood of additional schedule delays. Each month, the program updates its schedule risk analysis, based on the contractors' internal schedules as well as the program's perspectives and insight into specific technical risks. As of October 2016, the program's schedule risk analysis indicated that both contractors' certification dates would likely slip into early 2019.

The mounting schedule pressure on the Commercial Crew Program from the contractors' delays is amplified by NASA's need to provide a viable crew transportation option to the ISS before its current contract with Roscosmos, the Russian Federal Space Agency, runs out. The United States has spent tens of billions of dollars to develop, assemble, and operate the ISS over the past two decades, and NASA relies on uninterrupted crew access to help maintain and operate the station itself and conduct the research required to enable human exploration in deep space and eventually Mars, among other science and research goals. In 2015, the United States modified its contract with Roscosmos to provide crew transportation to the ISS for six astronauts through 2018 with rescue and return through late spring 2019. The contract extension was valued at \$491 million or approximately \$82 million per seat. NASA's contract with Roscosmos permits it to delay the use of the final seat by up to 6 months to late spring 2019, with a return flight approximately 6 months later.

NASA has not yet developed a contingency plan to ensure an uninterrupted presence on the ISS should the Commercial Crew Program experience further delays. The ISS program office stated there are other options it could consider to ensure uninterrupted access to the space station if neither contractor can provide crew transportation capabilities by the end of 2018; however, it may already be too late to pursue one of these options. If NASA determined it needed to purchase additional Soyuz seats, the process for contracting for those seats typically takes 3 years. In order to avoid a potential crew transportation gap in 2019, the contracting process would have needed to start in early 2016. In September 2016, senior NASA officials told us that they do not currently plan to purchase additional seats from Russia. The ISS program office stated that NASA could construct another "year in space" mission, similar to the mission undertaken by NASA astronaut Scott Kelly. According to the ISS program office, NASA and Roscosmos are discussing this option; however, there is no agreement in place. Under this scenario, an astronaut could begin a mission near the end of calendar year 2018 using

	one of the final Soyuz seats and would return to Earth via one of the Commercial Crew Program contractors' crew transportation systems approximately one year later in 2019. Finally, the NASA officials reported that NASA could consider negotiating the acquisition of "stand by" Soyuz seats, but the availability of those seats is dependent on Russia's plans for staffing the station. If NASA does not develop a viable contingency plan for ensuring access to the ISS in the event of further Commercial Crew delays, it risks not being able to maximize the return on its multibillion dollar investment in the space station.
Programmatic and Safety Risks Also Pose Challenges	In addition to Boeing and SpaceX's schedule challenges, both contractors face other risks that will need to be addressed to support their certification. This includes the contractors' ability to meet the agency's requirements related to the safety of their systems. These risks are not unusual; there are inherent technical, design, and integration risks in all NASA's major acquisitions, as these projects are highly complex and specialized and often push the state of the art in space technology. The Commercial Crew Program monitors risks through two lenses: programmatic risks potentially affect the program's cost and schedule or the performance of the crew transportation system, and safety risks could elevate the potential for the loss of crew. The contractors maintain their own risk management systems and do not always view their risks in the same way as the program.
Program's Top Risks for Boeing	The Commercial Crew Program's top programmatic and safety risks for Boeing are, in part, related to having adequate information on certain systems to support certification. For example, the Commercial Crew Program is tracking a risk about having the data it needs to certify Boeing's launch vehicle, ULA's Atlas V, for manned spaceflight. The Atlas V's first stage is powered by the Russian-built ULA-procured RD-180 engine, which has previously been certified to launch national security and science spacecraft but not humans. ULA and Commercial Crew Program officials have been working to get access to data about the engine design, so that they can verify and validate that it meets the program's human certification requirements. The program and Boeing report that access to the data is highly restricted by agreements between the U.S. and Russian governments. As an alternative, the program has stated that it is considering whether to certify the engine based on available data, but program officials believe doing so would be a high risk for the program. Boeing officials told us that they do not view this as a

safety risk because NASA will not certify the engines without reviewing the data it needs.

	The program is also tracking a risk about having adequate information on the parachute system. In March 2016, Boeing modified its previously approved parachute test plan by replacing six drop tests, which simulate select forces—for example, mass—on the parachute system for one full- scale test event, which simulates all aspects of a parachute system. Through discussions with the program, Boeing has increased the number of full-scale test events to five, with an option for two additional tests if deemed necessary. The program is in the process of reviewing the new test plan to determine if it will generate enough data for the program to evaluate the system. Regardless of whether the program approves Boeing's new parachute test plan, program officials told us that they plan to gather additional data on the performance and reliability of both contractors' parachute systems. NASA has several contractual options available to mitigate this risk, if needed. For example, NASA could choose to add additional analyses or parachute tests to the contract.
Program's Top Risks for SpaceX	The Commercial Crew Program's top programmatic and safety risks for SpaceX are, in part, related to ongoing launch vehicle design and development efforts. Prior to SpaceX's September 2016 loss of a Falcon 9 during pre-launch operations, the program was tracking several risks related to SpaceX's launch vehicle. SpaceX has identified five major block upgrades to its Falcon 9 launch vehicle. SpaceX officials told us that they have flown the first three block upgrades and are on track to implement the fourth and fifth block upgrades in 2017. Among other things, the updated design includes upgrades to the engines and avionics. The program is tracking a risk that there may not be enough time for SpaceX to implement these changes and get them approved prior to the first uncrewed flight test in November 2017. This test flight is a key activity to demonstrate how SpaceX's system meets the program's requirements. SpaceX needs to have a stable design to support certification. In addition to planned design changes, there could be unplanned design changes for the Falcon 9. During qualification testing in 2015, SpaceX identified cracks in the turbines of its engine. Additional cracks were later identified. Program officials told us that they have informed SpaceX that the cracks are an unacceptable risk for human spaceflight. SpaceX officials told us that they are working closely with NASA to eliminate these cracks in order to meet NASA's stringent targets for human rating. Specifically, SpaceX has made design changes that, according to its officials, did not result in any cracking during initial life

testing. Finally, both the program and a NASA advisory group consider SpaceX's plan to fuel the launch vehicle after the astronauts are on board the spacecraft to be a potential safety risk. SpaceX's perspective is that this operation may be a lower risk to the crew; NASA and SpaceX's risk evaluation is ongoing. NASA and SpaceX may also need to re-examine SpaceX's safety controls related to the fueling process if the investigation of the September 2016 Falcon 9 mishap identifies issues with the fueling of the vehicle.

At the time of our review, SpaceX also had other elements in its design that had not yet been completed and reviewed. SpaceX requested, and the program approved, proposals to split its critical design review into three reviews because portions of its design had not been ready at previous reviews. The critical design review is the time in a project's life cycle when the integrity of the product's design and its ability to meet mission requirements are assessed, and it is important that a project's design is stable enough to warrant continuation with design and fabrication. A stable design can minimize changes prior to fabrication, which can help avoid costly re-engineering and rework effort due to design changes. SpaceX's final planned design review was held in August 2016; however, the program reported that a number of outstanding areas, primarily related to ground systems, still needed to be reviewed. SpaceX officials told us these areas were reviewed in November 2016. Further, according to SpaceX, these separate reviews were in order to perform review of designs that were completed earlier than anticipated, to allow SpaceX and NASA teams to focus in greater detail on certain systems, and to accommodate design updates driven in part by changes to NASA requirements.

Program and Its	The Commercial Crew Program has identified the ability of it and its
Contractors Could Have	contractors to meet crew safety requirements as one of its top risks.
Difficulty Meeting Safety	NASA established the "loss of crew" metric as a way to measure the
Pequirements	safety of a crew transportation system. The metric captures the
Requirements	probability of death or permanent disability to one or more crew members.
	Under each contract, the current loss of crew requirement is 1 in 270,
	meaning that the contractors' systems must carry no more than a 1 in 270
	probability of incurring loss of crew. Near the end of the Space Shuttle
	program, the probability of loss of crew was approximately 1 in 90.
	Program officials told us that Commercial Crew is the first NASA program
	that the agency will evaluate against a probabilistic loss of crew
	requirement. They said that if the contractors cannot meet the agency
	loss of crew requirement at 1 in 270, NASA could still certify their systems

by employing operational alternatives. This would entail a potentially increased level of risk or uncertainty related to the level of risk for the crew.

Program officials told us their main focus is to work with the contractors to ensure that the spacecraft designs are robust from a safety perspective. The loss of crew metric and the associated models used to measure it are tools that help achieve that goal. For example, Boeing told us that in early 2016, it needed to identify ways to reduce the mass of its spacecraft. As Boeing found opportunities to reduce the spacecraft mass, the program stated that it also had to consider how implementing those design changes would affect its loss of crew analysis. According to the program, it is working with both contractors to address the factors that drive loss of crew risk through design changes or additional testing to gain more information on the performance and reliability of systems.

The Commercial Crew Program is tracking three main crew safety risks. First, the contractors' computer models may not accurately predict the loss of crew. These models are a weighted treatment of scenarios, likelihoods, and consequences throughout the flight, and are continually being updated by the contractors. According to program officials, they have been working closely with the contractors to improve their loss of crew models. For example, the program identified risk factors, such as bird strikes, that were not included in the contractors' models and worked to update them. Both contractors told us they have confidence in their models to accurately predict the loss of crew risk associated with their spacecraft. Second, the contractors' spacecraft may not be able to tolerate the micrometeoroid and orbital debris environment, which is the most significant driver of the loss of crew metric, according to the program's analysis. Both contractors have lowered this risk through testing, which provides insight into how well their systems perform in these environments, and by making design changes. If the contractors have to make future design changes to improve their spacecraft's performance in the debris environment, certification could be delayed significantly. Finally, if the contractors cannot meet the loss of crew requirement, there are several actions the Commercial Crew Program could take to help meet it; but, according to the program, these actions may not be enough to completely close the gap. The program has reported it is exploring options, such as the use of ISS cameras to conduct on-orbit inspections of the spacecraft.

Crew Program Has Visibility into Contractor Progress, but Maintaining Its Current Level of Visibility through Certification Could Add to Schedule Pressures	The Commercial Crew Program is using contractually-defined mechanisms to gain a high level of visibility into the contractors' crew transportation systems to achieve its goal of obtaining safe, reliable, and cost-effective access to and from the ISS. The program has developed productive working relationships with both contractors, but the level of visibility that the program has required thus far to assess the contractors' systems and ensure their safety has taken more time than the program or contractors anticipated. The early upfront investment in time may ultimately make the certification process go smoother, but the program office could face difficult choices as the program progresses about how to maintain the level of visibility into contractor efforts it feels it needs without adding to the program's schedule pressures. Further, the program faces potential workload challenges as it works to complete upcoming oversight activities, while completing others that were already behind schedule.
Crew Program Uses Contractually-Defined Mechanisms to Gain Visibility into Contractor Progress	The Commercial Crew Program included mechanisms in its firm-fixed- price contracts that it believed would enable it to gain the visibility into the contractors' technical efforts it needs to support a final certification decision. Contracting officials told us that the program included these mechanisms because it was concerned that the typical fixed-price inspection clauses may not give the program the level of visibility it felt it would need in order to certify the contractors' systems for human spaceflight. Using a firm-fixed-price contract for a human spaceflight development program represents a different way of doing business for NASA, which has typically used cost-reimbursement contracts for these efforts due to their complexity and the risks involved. Cost-reimbursement contracts require the government to maintain extensive visibility into a contractor's technical progress and financial performance. The visibility that NASA receives under its firm-fixed-price contracts with Boeing and SpaceX is similar to that of cost-reimbursement type contracts, with the exception that NASA does not receive any of the contractors' business- related cost and performance data such as earned value management. ⁵ In order to gain the needed visibility into the contractors' efforts, the Commercial Crew Program used a mix of standard and tailored contract clauses. The program began by leveraging NASA's Federal Acquisition

³Earned value management integrates information on a project's cost, schedule, and technical efforts for management and decision makers by measuring the value of work accomplished in a given period and comparing it with the planned value of work scheduled for that period and the actual cost of work accomplished.

Regulation Supplement, which contemplates NASA conducting inspections and other quality assurance requirements through "insight" and "oversight." In the supplement,

- insight is defined as the monitoring of contractor quality data and government-identified metrics and contract milestones, and any review of contractor work procedures and records; and
- oversight is defined as the government's right to concur or non-concur with the contractor's decisions affecting product conformity, and nonconcurrence must be resolved before the contractor can proceed.⁶

The Commercial Crew contracting officer explained that the program built upon what is in the NASA Federal Acquisition Regulation Supplement by including an additional "insight clause" in the contracts to set clear expectations that the program intended to obtain extensive information about how the contractors were meeting contract requirements. For example, the Commercial Crew contracting officer told us that one such expectation is that the contractors will provide the program access to virtually all data produced under or relevant to the contract, including subcontractor data.

The insight clause includes three mechanisms for the program to gain visibility into what progress the contractors are making and how the contractors are performing work. The clause also requires each contractor to develop an insight implementation plan for how it will provide access and data to NASA and facilitate the program's visibility into its crew transportation systems. Table 2 describes the three mechanisms and provides examples of how NASA has used them to gain visibility into the contractors' progress.

⁶NASA FAR Supplement § 1846.401.

Table 2: Commercial Crew Program Uses Three Contractually-Defined Mechanisms to Gain Visibility into the Contractors' Crew Transportation Systems

Contract's insight clause mechanisms	Examples of how the Commercial Crew Program uses insight mechanisms to facilitate visibility	
 Quality Assurance The clause states that the Commercial Crew Program will use a risk-based analysis to perform quality assurance functions and devote its insight resources to the most safety-critical items identified by the program. Quality assurance activities may include process witnessing, product examination, audits, and reviewing documents or data, among others. Officials told us that process witnessing—observing contractors conduct a process—is 	 The Commercial Crew Program identified SpaceX's thermal protection system as a high-risk hazard. As a result, the program's quality assurance team witnessed SpaceX engineers installing spherical tiles on their crew capsule's heat shield to verify the required process was followed. The Commercial Crew Program identified Boeing's upcoming integration of composite overwrapped pressure vessels as a technically difficult and high-risk item. As a result, the program planned to conduct a product examination to verify Boeing's compliance with inspection requirements 	
one of the most robust methods for obtaining visibility into contractors' progress.	compliance with inspection requirements.	
 Working Level Insight Working level insight is used to gain an understanding of the contractors' activities and provide information for eventual certification. Working level insight does not include approval or disapproval authority. Program officials told us they gain much of their visibility into the contractors' crew transportation systems through working level insight. Program officials regularly discuss technical issues with both contractors in forums, which have also helped facilitate strong working relationships between NASA and contractor engineers. 	 The Commercial Crew Program gained visibility into the contractors' parachute qualification testing plans through technical forums. As a result, the program has proposed six additional tests for each contractor to increase the reliability of their parachute systems. The Commercial Crew Program and SpaceX have worked together through technical forums to further understanding of SpaceX's planned fueling process. SpaceX plans to use densified propellant, or super-chilled liquid oxygen and rocket fuel, which has not traditionally been used for human spaceflight. To ensure the fuel remains chilled, SpaceX is planning to load the fuel after the astronauts are on board the spacecraft. The program is tracking a crew safety risk with respect to this approach. SpaceX has shared data related to its cargo missions using densified propellant and invited program officials to observe the loading process for those missions. 	
 Joint Test Team The joint test team includes the four NASA astronauts who will fly on the contractors' first crewed flight missions, as well as other program and contractor personnel. It allows the program to gain insight into crew-vehicle interface components, such as cockpit layouts or displays and controls, and allows the astronauts to provide non-binding feedback as the contractors work through their designs. 	 Program officials told us the joint test team has been involved with Boeing's development of engineering and training simulators, and has participated in simulations for various phases of space flight. SpaceX officials told us the joint test team has been coordinating with its engineers as they develop and evaluate displays and controls, as well as finalize their spacesuit design. 	

Source: GAO analysis of NASA data. | GAO-17-137

The visibility that the Commercial Crew Program gains through the use of these contract mechanisms is designed to assist in its oversight and final certification of the contractors' crew transportation systems, as shown in figure 4.



Figure 4: Elements of Commercial Crew Program's Insight, Oversight, and Final Certification Process

Source: GAO analysis of National Aeronautics and Space Administration documents. | GAO-17-137

The Commercial Crew Program and its contractors have made progress working together to ensure the program obtains the level of visibility that it feels it needs to achieve certification. All three organizations said that their relationships and communication have improved over the course of the contract, even as they have addressed difficult issues. For example, program officials said that Boeing is doing a much better job of communicating NASA's safety requirements to ULA than it did during previous contract phases, and that ULA has made great strides embracing a crew safety culture as demonstrated through its efforts to understand the program's crewed flight requirements. We also heard a strong consensus across several independent bodies and the contractors that the Commercial Crew program manager is providing critical leadership to the program to help the NASA workforce operate effectively in the firm-fixed-price contract environment. For example, Aerospace Safety Advisory Panel officials told us that, while they originally had concerns about how the firm-fixed-price environment would work for a human spaceflight development, they are confident in the progress of the program and its future success because of the program manager's leadership and transparency.

Sustaining Program's Level of Visibility Might Be Difficult as Schedule Pressure Builds

Page 21

The Commercial Crew Program has developed productive working relationships with both contractors, but the level of visibility that the program has required thus far has also taken more time than the program or contractors anticipated. The program's standing review board has stated that the contract is structured to allow NASA unprecedented levels

	of visibility, but that it was intended to be used primarily for high-risk areas. However, the standing review board found, and both contractors told us, that the program has requested high levels of visibility on most items and there are signs that the contractors' patience is waning. Both contractors expressed concerns that the program requests more interaction and data than they originally anticipated at the time of the contract award. For example, Boeing and SpaceX officials told us that the program often requests additional in-person engagement with their engineers, such as repeat presentations to multiple boards on the same technical issue, and has also asked for the same data in multiple formats or from multiple stakeholders. Program officials told us that they are constantly working to find a balance between obtaining the visibility they need to be able to eventually certify the crew transportation systems for human spaceflight while giving the contractors room to independently work through issues for their systems.
	As the Commercial Crew Program progresses, the program office could also face difficult choices about how to maintain the level of visibility into contractor efforts it feels it needs without adding to the program's schedule pressures. Independent review bodies, including the standing review board, the Aerospace Safety Advisory Panel, and the NASA Advisory Council-Human Exploration and Operations committee, expressed concern that the program may not have the capacity to sustain the level of visibility it has had to date and still meet the current certification schedule. The early upfront investment in time may ultimately make the certification process go smoother, but finding the right balance of visibility, and recognizing that a high level of visibility takes time and may impact the schedule, will be especially important as the contractors approach final certification when the government will need to determine if the systems are safe enough for human spaceflight.
Program Office Workload Is an Emerging Schedule Risk	Program officials told us that one of their greatest upcoming challenges will be to keep pace with the contractors' schedules so that the program does not delay certification. Specifically, they told us they are concerned about an upcoming "bow wave" of work because the program must complete two oversight activities—phased safety reviews and verification closure notices—concurrently in order to support the contractors' ISS design certification reviews, uncrewed and crewed flight test missions, and final certification.
	The Commercial Crew Program is working to complete its three-phased safety review, which will ensure that the contractors have identified all

safety-critical hazards and implemented associated controls, but it is behind schedule. Both the contractors and the program have contributed to these delays. In phase one, Boeing and SpaceX identified risks in their designs and developed reports on potential hazards, the controls they put in place to mitigate them, and explanations for how the controls will mitigate the hazards. In phase two, which is ongoing, the program reviews and approves the contractors' hazard reports, and develops strategies to verify and validate that the controls are effective. In phase three, the contractors will conduct the verification activities and incrementally close the reports.

The Commercial Crew Program's review and approval of the contractors' hazard reports have taken longer than planned. The program originally planned to complete phase two in early 2016 but currently does not expect to complete this phase until June 2017. The Commercial Crew Program has a goal of reviewing hazard reports within 8 weeks of receiving them, but a recent report by the NASA Office of Inspector General found that the reviews are taking longer than anticipated and a backlog has developed.⁷ In response to the Inspector General's report, NASA officials noted that, while the timeliness of the hazard review process is important, what is more important is having thorough, detailed hazard reports in order to understand safety risks and ensuring the safety of each system. As of October 2016, the Commercial Crew Program had approved 117 of the anticipated 195 hazard reports and planned to approve approximately half of the remaining reports for both contractors by the end of 2016. Program officials told us that the hazard reports that are still open are related to items that they would not expect to be closed because they involve some of the more complicated design work that the contractors have not yet finalized. Program officials also pointed out other ways that the contractors have contributed to phase two delays, including receiving incomplete hazard reports that required several iterations before the program could begin its formal review.

The Commercial Crew Program's verification closure notice process, which is used to verify that the contractors have met all requirements, is one of the other key oversight activities and potential workload challenges for the program. The program is completing that process concurrently with the phased safety reviews. The verification closure process is

⁷NASA Office of the Inspector General, *NASA's Commercial Crew Program: Update on Development and Certification Efforts*, IG-16-028 (Washington, D.C.: Sept. 1, 2016).

initiated by the contractor when it provides the program with data and evidence to substantiate that it has met each requirement, and is completed when the program has reviewed and approved the contractor's evidence to verify that each requirement has been met. A verification closure notice is required for each of the 332 ISS requirements, which are applicable to anyone who docks with the station, and the 280 Commercial Crew Program requirements. The Commercial Crew Program must also approve a subset of verification closure notices before key tests or milestones can occur. For example, the ISS requirements must be met before SpaceX and Boeing's uncrewed flights to the ISS, which are currently planned for November 2017 and June 2018, respectively. The program's ability to smooth its workload is limited because the contractors generally control their development schedules. Proposed changes to the Boeing and SpaceX schedules could help alleviate some of the concurrency between the program's phased safety reviews and verification closure process.

Conclusions

NASA's Commercial Crew Program is a multibillion dollar effort intended to end the United States' reliance on Russia to maintain an uninterrupted presence on the ISS. To do so, NASA embarked on a different way of doing business. It awarded firm-fixed-price contracts to Boeing and SpaceX that transferred the financial risks to the contractors while giving them freedom to develop unique transportation systems that meet NASA's standards. An independent review group initially raised concerns about how well this model would work for a human spaceflight program. Parts of the new business model have worked relatively well and NASA has had the visibility it needs into the technical details and risks of each system. Gaining this level of visibility has taken more time than the program or contractors anticipated, but the early upfront investment in time should ultimately make the certification process go smoother. In addition, while the Commercial Crew Program should be mindful about placing undue burdens on its contractors, it ultimately has the responsibility for ensuring the safety of U.S. astronauts, and its contracts with Boeing and SpaceX give it deference to determine the level of insight required to do so.

When the current phase of the Commercial Crew Program began, there was widespread acknowledgment that the contractors' development and certification schedules were aggressive, and the anticipated schedule risks have now materialized. Both contractors' certification dates have been delayed into 2018, and the program's analysis indicates that neither contractor is likely to be ready until 2019. NASA has purchased seats for

	U.S. astronauts on the Russian Soyuz vehicle, so that it can maintain an uninterrupted presence on the ISS. But those seats will run out in spring 2019, at the latest, and it generally takes 3 years for NASA and Russia to negotiate the purchase of additional seats. If delays on the Commercial Crew Program persist, having contingency plans, including options to expedite the purchase of additional Soyuz seats, will become increasingly important to ensure an uninterrupted U.S. presence on the ISS. Without a viable contingency plan that has been communicated to Congress, NASA puts at risk its ability to maximize the utility of the ISS and the return on the multibillion dollar investment it has made in the space station.
Recommendation for Executive Action	In order to ensure that the United States has continued access to the ISS if the Commercial Crew Program's contractors experience additional schedule delays, we recommend the NASA Administrator develop a contingency plan for maintaining a presence on the ISS beyond 2018, including options to purchase additional Russian Soyuz seats, and report to Congress on the results.
Agency Comments and Our Evaluation	 We provided a draft of this report to NASA for comment. In written comments, NASA agreed with our recommendation and intends to develop a contingency plan by mid-March 2017. These comments are reproduced in Appendix III. NASA also provided technical comments, which have been addressed in the report, as appropriate. We are sending copies of the report to the NASA Administrator and interested congressional committees. In addition, the report will be available at no charge on GAO's website at http://www.gao.gov. If you or your staff have any questions about this report, please contact me at (202-512-4841 or chaplainc@gao.gov. Contact points for our Offices of Congressional Relations and Public Affairs may be found on the last page of this report. GAO staff who made major contributions to this report are listed in Appendix IV. Cristina T, Chaplain.

Cristina T. Chaplain Director, Acquisition and Sourcing Management

Appendix I: Objectives, Scope, and Methodology

The objectives of our review were to assess (1) the extent to which the contractors have made progress towards certification and the potential effects of any certification delays on the National Aeronautics and Space Administration's (NASA) access to the International Space Station (ISS); (2) the major programmatic and safety risks facing the program and the contractors; and (3) the extent to which the program has visibility into the contractors' efforts.

To assess the contractors' progress towards certification, we obtained and reviewed program and contractor documents, including monthly and quarterly updates as well as monthly schedule summaries, from March 2016 through December 2016. We interviewed program and contractor officials to discuss the contractors' recent progress as well as their upcoming events and any expected delays. To identify total delays to date, we compared original contract schedules to Boeing's October 2016 working schedule and SpaceX's November 2016 working schedule, which identify their most recent proposed delays to some milestones. To identify whether the contractors have introduced compression into their schedules, we judgmentally selected four key events and analyzed the movement of these key events relative to each other. Based on our review of program and contractor documents, we selected the contract's acceptance events-the ISS design certification review and final certification review—as well as the uncrewed and crewed flight tests to conduct this analysis. We selected the acceptance events, as these occur when NASA approves a contractor's designs and acknowledges that the contractor's work is complete and meets the requirements of the contract. We selected the two flight tests for each contractor, as they are intended to test key system capabilities including the ability to launch, dock with the ISS, and return safely to Earth. Finally, to assess the potential effects of any certification delays on NASA's access to ISS, we reviewed information from NASA's budget, which includes the planned ISS launch manifest, and its contract with the Russian Federal Space Agency for transportation on the Soyuz vehicle. We also obtained information from the ISS program and the NASA Associate Administrator to determine if the agency had developed contingency plans to mitigate the effects of any certification delays on its access to the ISS.

To assess the programmatic and safety risks for the Commercial Crew Program and its contractors, we obtained and reviewed monthly and quarterly reports, as well as the risks tracked in both the program's and the contractors' risk management systems, from March 2016 through December 2016. We interviewed program and contractor officials with knowledge of the technical risks to understand the risks and potential impacts and how they are planning to mitigate those risks.

To assess how the program obtains visibility into its contractors' systems and efforts, we reviewed the program's contracts with its two contractors. In particular, we reviewed the contract "insight" clause, which outlines three mechanisms available to the program for obtaining visibility. We interviewed program officials in order to understand the three mechanisms and how they are used to gain visibility. We also interviewed officials from both contractors to gain their perspectives on the insight mechanisms. We also analyzed how NASA obtained visibility into contractor efforts at key events. We defined key events as those that are necessary for final certification. We selected three key events to examine for each contractor. We chose one historical event, so we could assess how the program had gained visibility over an entire event, and one upcoming event in both 2016 and 2017, in order to understand how the program obtains visibility in advance of an event. For each event, we obtained detailed information on how NASA obtained visibility and analyzed supporting documentation for these events to corroborate the information we obtained from NASA officials. In this report, we used these events as examples when describing how the program uses its three insight mechanisms and when describing the program's relationships with its contractors. We also interviewed the program and contracting officials to obtain their perspectives on the level of visibility that the program has received into the contractors' systems thus far. Finally, we analyzed program documentation and interviewed program officials to understand the level of work that NASA needs to complete leading up to certification. We assessed the timing of NASA's reviews and spoke with program officials to determine if the program's workload could be affected by the contractors' schedules.

For all three objectives, we met with officials from all three organizations that provide NASA with independent assessments of the program: the program's standing review board, the NASA Advisory Council-Human Exploration and Operations subcommittee, and the Aerospace Safety Advisory Panel. We spoke with these three groups to gain their perspectives on the program's oversight of each contractor's technical risks and schedules as well as the program's level of visibility into the contractors' systems.

We conducted this performance audit from March 2016 to February 2017 in accordance with generally accepted government auditing standards. Those standards require that we plan and perform the audit to obtain sufficient, appropriate evidence to provide a reasonable basis for our findings and conclusions based on our audit objectives. We believe that the evidence obtained provides a reasonable basis for our findings and conclusions based on our audit objectives.

Appendix II: Commercial Crew Program Phases and Participants

The Commercial Crew Program is a multi-phased effort that began in 2010. Table 3 describes each phase, its purpose, the participants, and the level of funding provided by the National Aeronautics and Space Administration.

Table 3: Commercial Crew Program Phases, Contractors, and Level of Funding

Phase of the Commercial Crew Program and the Year It Began	Companies Involved and Level of Funding
Commercial Crew Development, Round 1 (2010)	Blue Origin - \$3.7 million
Space Act agreement	Boeing - \$18 million
The first phase of the program included the development and	 Paragon Space Development Corporation - \$1.4 million
maturation of systems, such as spacecraft or launch abort	 Sierra Nevada Corporation - \$20 million
systems.	United Launch Alliance - \$6.7 million
Commercial Crew Development, Round 2 (2011)	Blue Origin - \$22 million
Space Act agreement	Boeing - \$92.3 million ^a
The second phase was to further aid development and	 Sierra Nevada Corporation - \$80 million^a
demonstration of transportation capabilities, among other	SpaceX - \$75 million
goals.	Alliant Techsystems, Inc. – unfunded
	Excalibur Almaz Inc. – unfunded
	United Launch Alliance – unfunded
Commercial Crew Integrated Capability (2012)	 Boeing - \$460 million^b
Space Act agreement	 Sierra Nevada Corporation - \$212.5million^b
This phase included development of crew transportation capabilities and contractors' tests to verify, validate, and mature integrated designs.	 SpaceX - \$440 million^b
Certification Products Contracts (2012)	Boeing - \$9.993 million
Contract	Sierra Nevada Corporation - \$10 million
This phase included the development of certification plans and data products to demonstrate how the contractors' systems would meet the agency's flight safety and performance requirements.	SpaceX - \$9.570 million
Commercial Crew Transportation Capability (2014)	Boeing - \$4.2 billion
Contract	SpaceX - \$2.6 billion
The final phase of the program is intended to result in NASA's final certification of the commercial crew transportation systems.	

Source: GAO analysis of NASA data. | GAO-17-137

Note: Space Act agreements are NASA's other transaction authority.

^aNASA later funded an additional \$20.6 million to Boeing and \$25.6 million to Sierra Nevada Corporation by exercising optional, pre-negotiated milestones under the agreements, to accelerate development.

^bNASA later funded an additional \$20 million to Boeing, \$20 million to SpaceX, and \$15 million to Sierra Nevada Corporation by exercising optional, pre-negotiated milestones under the agreements, to accelerate development.

Appendix III: Comments from the National Aeronautics and Space Administration

	National Aeronautics and Space Administration Headquarters Washington, DC 20546-0001 FEB 8 2017	
Reply to Attn of:		
	Human Exploration and Operations Mission Directorate	
	Ms. Cristina T. Chaplain Director Acquisition Sourcing Management United States Government Accountability Office Washington, DC 20548	
	Dear Ms. Chaplain:	
	The National Aeronautics and Space Administration (NASA) appreciates the opportunity to review and comment on the Government Accountability Office (GAO) draft report entitled, "NASA Commercial Crew Program: Schedule Pressure Increases as Contractors Delay Key Events" (GAO-17-137), dated January 10, 2017.	
	In the draft report, GAO makes one recommendation to the NASA Administrator intended to ensure continued U.S. access to the International Space Station (ISS).	
	Specifically, GAO recommends the following:	
	Recommendation 1: In order to ensure that the United States has continued access to the ISS if the Commercial Crew Program's contractors experience additional schedule delays, GAO recommends that the NASA Administrator develop a contingency plan for maintaining a presence on the ISS beyond 2018, including options to purchase additional Russian Soyuz seats, and report to Congress on the results.	
	Management's Response: NASA concurs with the recommendation. NASA will develop a contingency plan for maintaining a presence on the ISS beyond 2018 if the Commercial Crew Program's partners experience additional schedule delays. NASA anticipates the contingency plan to be ready in approximately six weeks.	
	Estimated Completion Date: March 13, 2017	
-1		

2 Once again, thank you for the opportunity to comment on the subject draft report. If you have any questions or require additional information, please contact Michelle Bascoe at (202) 358-1574. Sincerely, 00 William H. Gerstenmaier Associate Administrator For Human Exploration and Operations

Appendix IV: GAO Contact and Staff Acknowledgments

GAO Contact	Cristina Chaplain, (202) 512-4841 or chaplainc@gao.gov
Staff Acknowledgments	In addition to the contact named above, Molly Traci, Assistant Director; Ron Schwenn, Assistant Director; Carly Gerbig; Laura Greifner; Kurt Gurka; Michael Kaeser; Katherine Lenane; Roxanna T. Sun; and Kristin Van Wychen made significant contributions to this report.

GAO's Mission	The Government Accountability Office, the audit, evaluation, and investigative arm of Congress, exists to support Congress in meeting its constitutional responsibilities and to help improve the performance and accountability of the federal government for the American people. GAO examines the use of public funds; evaluates federal programs and policies; and provides analyses, recommendations, and other assistance to help Congress make informed oversight, policy, and funding decisions. GAO's commitment to good government is reflected in its core values of accountability, integrity, and reliability.
Obtaining Copies of GAO Reports and Testimony	The fastest and easiest way to obtain copies of GAO documents at no cost is through GAO's website (http://www.gao.gov). Each weekday afternoon, GAO posts on its website newly released reports, testimony, and correspondence. To have GAO e-mail you a list of newly posted products, go to http://www.gao.gov and select "E-mail Updates."
Order by Phone	The price of each GAO publication reflects GAO's actual cost of production and distribution and depends on the number of pages in the publication and whether the publication is printed in color or black and white. Pricing and ordering information is posted on GAO's website, http://www.gao.gov/ordering.htm.
	Place orders by calling (202) 512-6000, toll free (866) 801-7077, or TDD (202) 512-2537.
	Orders may be paid for using American Express, Discover Card, MasterCard, Visa, check, or money order. Call for additional information.
Connect with GAO	Connect with GAO on Facebook, Flickr, LinkedIn, Twitter, and YouTube. Subscribe to our RSS Feeds or E-mail Updates. Listen to our Podcasts. Visit GAO on the web at www.gao.gov and read The Watchblog.
To Report Fraud.	Contact:
Waste, and Abuse in Federal Programs	Website: http://www.gao.gov/fraudnet/fraudnet.htm E-mail: fraudnet@gao.gov Automated answering system: (800) 424-5454 or (202) 512-7470
Congressional Relations	Katherine Siggerud, Managing Director, siggerudk@gao.gov, (202) 512-4400, U.S. Government Accountability Office, 441 G Street NW, Room 7125, Washington, DC 20548
Public Affairs	Chuck Young, Managing Director, youngc1@gao.gov, (202) 512-4800 U.S. Government Accountability Office, 441 G Street NW, Room 7149 Washington, DC 20548
Strategic Planning and External Liaison	James-Christian Blockwood, Managing Director, spel@gao.gov, (202) 512-4707 U.S. Government Accountability Office, 441 G Street NW, Room 7814, Washington, DC 20548